



- \* Millwork 2.25" Casing and 2.75" Base Pre- Finished Oak, Honey Oak stain. Buyer may choose other types, styles, or colors offered by builder. Specific selection may constitute an upgrade.
- \* Cabinets: Oak kitchen and bath cabinetry with flat panel door style, in Honey Oak stain. Buyer may choose other types, stains, or styles, offered by builder. Specific selection may constitute an upgrade.
- \* Counter Tops: Post Form laminate countertops with raised roll edge, stock pattern color. Buyer may choose from countertops offered by builder or elect to upgrade or downgrade based on established countertop allowance.
- \* Closet Shelving: All clothes closet shelving is vinyl-coated wire with at least one shelf and rod in each clothes closet. Four shelves in linen closet.
- \* Exterior Deck: Decks will be treated or wolmanized dimensional lumber with Cedar Decking and Rail
- \* Underlayment: ¼" Structure Wood or equal (by flooring contractor and included in flooring allowance)

#### **THERMAL AND MOISTURE PROTECTION**

- \* Foundation: Hydrocide waterproofing or equal applied to exterior walls below grade
- \* Basement, Garage, Walls: 3 ½" R-11 friction fit batts
- \* Exterior Walls: 3 ½" R-13 friction fit batts or 5 ½" R-19 for 2x6 walls
- \* Boxsill: 6" R-19 Kraft-faced batts stapled in place
- \* Overhead: 9½" R-30 Kraft-faced batts stapled in place
- \* House to Garage Wall: 3 ½" R-13 Kraft-faced batts stapled in place
- \* Garage Under: 9 ½" R-30 friction fit batts with 5/8" Tuff-R
- \* Cathedral Ends: 3 ½" R-13 Kraft-faced batts stapled in place
- \* Small Lids: 12" R-38 Kraft-faced batts stapled in place
- \* Flat Lids: 12" R-38 Blown in Fiberglass (garage ceilings extra)
- \* Baffles: Placed in every truss
- \* Shingles: Certain Teed Landmark 30 color selected by buyer.
- \* Siding: Double 4 vinyl siding, color selected by buyer, with white aluminum soffits and fascia,
- \* Gutters and Downspouts: White, seamless .32" thick aluminum gutter with 0.24" thick aluminum downspouts.

#### **DOORS AND WINDOWS**

- \* Exterior Doors: Front entry doors – Fiberglass 6 panel  
Garage to House – Steel 6 panel
- \* Patio Doors: Gerkin sliding, white vinyl, insulated Low E glass
- \* Garage Overhead: Overhead door 16' x 7' steel, raised panel insulated with opener  
2 remotes and 1 keyless (windows if any as shown on plans)
- \* Interior Doors: Pre-hung – oak hollow core with oak veneer jamb  
Bi-fold – oak hollow core oak veneer jamb
- \* Finish Hardware: Entrance, privacy, and passage locks are Schlage Plymouth style.  
Satin Nickel finish is standard, deadbolt at front entry door
- \* Mirrors: Polished edge 36" high (width will be 6" less than vanity width)
- \* Windows: Gerkin sliders, white vinyl with insulated Low E glass

### **FINISHES**

- \* Gypsum Wall Board: **Ceiling** – 5/8" or 1/2" high strength with spatter spray finish  
**Walls** – 1/2" sheetrock with spray finish  
**Garage** – 5/8" sheetrock with one coat tape
- \* Floor Covering: Vinyl in entry, kitchen, baths, and laundry  
Carpet in all other finished areas  
Ceramic tile around fireplace and hearth  
Buyer may choose from floor coverings offered by builder, or elect to upgrade or downgrade based on established flooring allowance.
- \* Paint & Stain: Interior walls and ceilings will be primed once and finish coated using a single color selected by buyer. Multiple colors available as an upgrade.  
Front entry door will be latex enamel color selected by buyer. All other exterior doors will be painted white.  
All trim and interior doors will be pre-finished. All window sills, wall caps etc. finished to match trim.

### **SPECIALTIES**

- \* Toilet and Accessories: One toilet paper holder per bathroom.  
One 24" towel bar per bathroom.  
One towel ring per 1/2 bathroom.  
All accessories in chrome finish

### **EQUIPMENT:**

- \* Appliances: Stainless steel, dishwasher, refrigerator, microwave and range.  
Allowance includes delivery and set up  
Buyer may choose from appliances offered by builder or elect to upgrade or downgrade based on an established appliance allowance.

## PLUMBING

### \* Fixtures:

1-Aqua Glass 314936 48"x35" White shower with Moen 2353 Posi-Temp single handle control

1-Aqua Glass 826036 60x36 white fiberglass tub/shower with Moen 2353 Posi-Temp single handle control

3-Mansfield 130-160 white toilets with seats and supplies

2-Mansfield 1916 SRO 19.5x16.5 white self rimming lavs with Moen 4621 single handle control

1-Mansfield 190 24"x21" white pedestal lav with Moen 4625 single handle faucet

1-Dayton Elite DSE3322 33x21 20 gauge stainless steel self rimming double compartment sink with Moen 7432 single handle control with hose and spray attachment

1-Insinkerator Model Badger 5 garbage disposal (wiring by electrical contractor)

1- Plumbing connection for dishwasher

1- Water line for refrigerator

1- Guy Gray washer box

2-Woodford 17 frostproof sillcocks (location by builder unless prearranged)

1-40 gal. Guardian Hi-Eff. Glass lined water heater (venting by HVAC contractor)

1- By Pass set up for future water softener

1- 3/4" water meter set up (wiring by electrician)

Waste rough in under concrete for future basement bath.

2" floor drain, in furnace area.

Radon Pit with 3" piping to attic.

All plastic pipe and fittings to complete waste and vent piping.  
All copper and plastic pipe and fittings to complete supply lines  
All black pipe and CST pipe and fittings to complete gas lines from meter to furnace, water heater and fireplace ( any other gas appliance requiring gas and or installation will be extra)  
All in ground or non walkout basements will include a sump pump and piping to ext. Sump pumps are not included for walk out basements.

## HEATING AND AIR CONDITIONING

### \* Equipment:

Lennox G43UF-70 70,000 BTU 92% eff. Furnace

Lennox 13ACD30 30,000 BTU 14 Seer high eff. AC

Venting for water heater, bath fans, range and dryer

Provide all duct work and registers

Provide and install Programmable Thermostat

Start up furnaces and air conditioners

## ELECTRICAL

### \* Electrical Services:

Wire and panel adequate in size to accommodate temporary furnaces, air compressor and power tools. All outlets and switches as required by local code. Additional outlets, switches, TV or phones will be \$40.00

Pre-wiring for 5 TV

Pre-wiring for 4 telephones

Laundry room to have 100V washer & 220V dryer plugs

Install weatherproof plugs

Supply and install 3 bath fan lights

2 Ceiling fan rough ins (1 switch for ea. Inc)

Install wiring for gas furnace

Install wiring for electric air conditioner

Hook up all electrical appliances - dishwasher, disposal & oven

All switches shall be the 15 AMP quiet type-white

All plugs shall be ground type - white

All plates for switches and plugs are to be white

Chime wiring only for 1 door

Supply and install 7 smoke detectors

200AMP services

Install 2 water meter wires

Also inc. are 2 recess lights flat trim, and 1 recess eye ball